
CERTIFIED klk 09/25/2012 4:54:15 PM



END VIEW

TIE IN SCHEDULE				
MK	DESCRIPTION	SIZE/TYPE		
T1	PROCESS AIR INLET	8" 150# RF CS		
T2	19% AQUEOUS AMMONIA INLET	1/2" 150# RF SS		
T3	INSTRUMENT AIR	1/2" 150# RF SS		
T4	AMMONIA/AIR OUTLET	10" 150# RF SS		
T5	SERVICE WATER FLUSH	1/2" 150# RF SS		



By Andy Bilmanis on Oct 09, 2012

This review does not supersede requirements of purchase order, design drawings, specifications, codes or regulations. The contractor / supplier is not relieved from responsibility for errors or omission.

- 1. FOR PLAN VIEW SEE DWG. NO.: G-25014-01.
 2. FOR ELEVATION VIEW SEE DWG. NO.: G-25014-02.
 3. FOR ISO VIEW SEE DWG. NO.: G-25014-04.

4. ALL DIMENSIONS \pm 1/4".

INTEGRATED FLOW SOLUTIONS

6461 REYNOLDS RD, TYLER, TEXAS, USA 75708 PHONE NUMBER: +1 (903) 595-6511
EMAIL: SUPPORT@IFSOLUTIONS.COM

THIS DRAWING IS THE PROPERTY OF INTEGRATED FLOW SOLUTIONS AND	
SHALL NOT BE REPRODUCED, COPIED, LENT, NOR USED FOR ANY PURPOSE DTHER THAN THAT WHICH IT IS FURNISHED EXCEPT BY WRITTEN PERMISSION.	
THER THAN THAT WHICH IT IS FURNISHED EXCEPT BY WRITTEN PERMISSION	

1	25JUN12	REVISED TAGGING PER CUSTOMER COMMETNS	RM	RC
0	22FEB12	APPROVED FOR CONSTRUCTION	RM	RC
В	06JAN12	ISSUED FOR CUSTOMER APPROVAL	RM	RC
Α	15DEC11	ISSUED FOR CUSTOMER APPROVAL	RM	RC
REV.	DATE	DESCRIPTION	DES	ENG

PROJECT: GAINESVILLE RENEWABLE ENERGY CENTER (GREC) CUSTOMER NAME: FUEL TECH

END USER: GAINESVILLE RENEWABLE ENERGY CENTER (GREC) SYSTEM DESCRIPTION: AMMONIA FLOW CONTROL SKID (AFCU)

CUSTOMER PO#: 34081-1 ESTIMATED DRY WEIGHT: 5900 LBS. ESTIMATED OPERATING WEIGHT: 5950 LBS.

		ARRANGI		
AMMONIA	FLOW	CONTROL	SKID	(AFCU)

ENT No.: P00090756					
ALE: 1/2"=1'-0"	SECTION	JOB	SHEET	TOTAL SHEETS	REV.
.: D. POLLAN	G - 25014- 03			4	1